


# Howard A. Hanson Dam Seepage Issues, Risk Assessment and Repairs

Richard Smith, PG  
Seattle District  
U.S. Army Corps of Engineers  
May 2012




®

US Army Corps of Engineers  
**BUILDING STRONG**®



Authorized  
Personnel  
Only

# Project Location




## Purpose

- Flood risk mitigation (1950)
- Low flow augmentation (1950)
- M&I water storage (1998)
- Ecosystem restoration (2000).



# Purpose/Operation




- Original authorized pool = 1141 feet (summer/fall river flow augmentation).
- Section 1135 project = 1147 feet (beneficial use for fish).
- Phase I Additional Water Storage = 1167 feet.
- Phase II Additional Water Storage = 1177 feet.
- Design flood pool = 1206 feet.
- PMF = 1224 feet (top of dam = 1228 feet).





# Dam Features & Design


- Embankment is permeable and piping/erosion resistant.
- Right abutment seepage and piping risk known pre-dam construction.
- Upstream and downstream slope treatment designed to control seepage.
- Drainage tunnel added after dam construction (1969).
- Abutment monitored & evaluated since construction.



# Geologic Setting



# Geologic Setting



# Consequences


- 32,000 residents and 65,000 jobs
- >80,000 commuters/day
- 4<sup>th</sup> largest continuous warehousing district in the US
- Hub for two major seaports (4 million containers \$75B/year)
- \$45M in economic output/day
- King County comprises 2% of US Gross Domestic Product (same as Louisiana and Mississippi combined)
- Olympic Pipeline
- Railheads (BNSF and UP)
- Electrical substations serving 35,000 residents.



1940



# January 2009 Flood



Pool of Record

Vertical Tunnel Drains

Turbidity from Tunnel Drain


Depression on Upstream Face



# Investigations



Unfiltered Vertical Drains



No Hydraulic Connection  
Between Turbid Drain  
and Depression

Depression Caused by Collapse  
of 1950's Era Exploration Tunnel.





Camera Survey & As-Built Records  
Dye Test



# 2009 Interim Repairs

## Grout Curtain


- 74,000 LF of drilling
- 550,000 gal. grout in overburden
- Substantially complete by 2009/2010 flood season



# 2009 Interim Repairs

## Drainage Tunnel Improvements

- Grouted vertical drain #25 and replaced with 2 new filtered vertical drains
- Installed 13 filtered horizontal drains.




# Effectiveness of Interim Measures

Reduced groundwater travel times

Preferential pathways lengthened

Increased tunnel drainage efficiency



Total tunnel drain flow increased relative to previous conservation pools.  
 Dye travel times positioned in areas  
 Water level regions (conservation pools).  
 Geophysical results indicate no preferential  
 conservation pool and 2010 conservation pool  
 pathways through new grout curtain.



# Risk Assessment

- Conducted concurrent with interim repairs
- Additional exploration.
- Review of dam design.
- Review of dam as-built records.
- Review of construction photos.
- **Potential failure modes analysis.**
- **Assessment of risk.**
- Congress lobbied by local electeds for funding and \$44M in supplemental O&M provided for additional interim repairs.



# Failure Modes of Concern

- **Short Path Seepage and Piping (Red).**
- **Drainage Tunnel Seepage and Piping (Blue).**




# Short Path Seepage Failure Mode

Downstream filter & drain

Lack of gravel drain


Filter incompatibility





zone 3 material could erode into and through the rock shell. Seepage modeling suggests saturation of filter material. Gravel drain ends at edge of rolled rock fill then incompatible material under greater than design flood pool conditions. rock shell and rock toe in contact with zone 3 filter.




# Failure Progression




## Short Path Seepage



# Risk Reduction Measures




# Risk Assessment Results for Right Abutment Seepage



- Failure probability is annualized to account for return frequency of various pools.
- Not allowed to show results with loss of life numbers.




# Drainage Tunnel Improvements



Existing Drainage Features




# Drainage Tunnel Improvements



New Vertical Drains



# Drainage Tunnel Improvements



New Horizontal Drains





# Completed Construction Activities



**Horizontal drains drilled from inside the tunnel.**




# 2011 Drainage Tunnel Improvements




Drilling new vertical drains  
 production hole for casing  
 Large diameter drilling through floor



# Short Path Dewatering Wells




# Short Path Seepage Repairs



Existing Tunnel With Improvements



# Short Path Seepage Repairs



Dewatering Wells



# Completed Dewatering System



**Production drilling for dewatering.**



**Completed system.**



# Other Failure Modes

PFM 3 – Spillway debris plugging




High velocity, modeled water flow toward spillway.  
PFM 17 – Left embankment erosion

Spillway plugged by debris  
would lead to dam overtopping.



# Spillway Debris Plugging



Original debris boom system barrier at elevation MFL 206 - not functional when spillway gates opened.



# New Log Boom System



**BUILDING STRONG®**

# New Rip Rap



Before



After



# Questions?

