

NW Hydro Operator's Forum

-WECC TESTING-

What's it all about?

Rod Gunther
PacifiCorp Energy
Hydro Resources

Good Reading Resource



Western Systems Coordinating Council


**TEST GUIDELINES FOR
SYNCHRONOUS UNIT DYNAMIC TESTING AND
MODEL VALIDATION**

Prepared by:


**WSCC
Control Work Group and
Modeling & Validation Work Group**

February 1997

Reference



Great Reading for the Engineer



Great Book

Electromagnetic and Electromechanical Machines

Leander W. Matsch

Professor of Electrical Engineering
University of Arizona

PacifiCorp Energy


- Has been testing and modelling since the 1990
- Whole industry has been on a learning curve.
- What to test, how to test, how to report?
- We started with OEMs
- Then on to consultants
- We are doing much of the testing and modelling ourselves (Hydro).


PacifiCorp

- We have created models of our equipment based upon standard IEEE transfer functions.
- The data, in PSSE format is turned over to our transmission planning group for review and verification and then they submit this data to the WECC.

Stabilizer Transfer Function

PSS2B.





t_r Filter time constant, sec
 v_{imax} Maximum error, pu
 v_{imin} Minimum error, pu
 t_c Lead time constant, sec
 t_b Lag time constant, sec
 k_a Gain
 t_a Time constant, sec
 v_{rmax} Maximum controller output
 v_{rmin} Minimum controller output
 k_c Excitation system regulation factor, pu
 k_f Rate feedback gain
 t_f Rate feedback time constant, sec

exst1 IEEE type ST1 excitation system

gentpj		esst4b		pss2a		hyg3		oel1	
Ipdo	7	Tr	0.0167	J1	1	Pmax	1	Ifdset	2.5
Ippdo	0.035	Kpr	35	K1	0	Pmin	0	Ifdmax	3.3
Ipqo	0	Kir	10	J2	3	Cflag	1	Tpicku	20
Ippqo	0.035	Ta	0	K2	0	Rgate	0	Runbac	0
H	3	Vrmax	1	Tw1	7.5	Relec	0.05	Tmax	999
D	0	Vrmin	-0.87	Tw2	7.5	Td	0.02	Tset	999
Ld	1	Kpm	1	Tw3	7.5	Tf	0.02	Ifcont	2.5
Lq	0.75	Kim	0	Tw4	0	Tp	0.1	Vfdflag	0
Lpd	0.32	Vmmax	99	T6	0	Velop	0.1		
Lpq	0.75	Vmmin	-99	T7	7.5	Velcl	-0.1		
Lppd	0.23	Kg	0	Ks2	1.27	K1	0.01		
Lppq	0.23	Kp	2	Ks3	1	K2	1.5		
Ll	0.15	Angp	0	Ks4	1	Ki	0.75		
S1	0.15	Ki	0	T8	1	Kg	2		
S12	0.45	Kc	0.08	T9	0.2	Tt	0.2		
Ra	0.003	Xl	0	n	1	db1	0		
Rcomp	0	Vbmax	6	m	5	eps	0		
Xcomp	-0.05	Vgmax	999	Ks1	7	db2	0		
Kis	0.07			T1	0.1	Tw	1		
				T2	0.0167	At	1		
				T3	0.1	Dturb	0.5		
				T4	0.0167	qnl	0		
				Vstmax	0.1	H0	1		
				Vstmin	-0.1	Gv1	0.07		
				a	1	Pgv1	0		
				Ta	0.1	Gv2	0.23		
				Tb	0.0167	Pgv2	0.2		
						Gv3	0.57		
						Pgv3	0.8		
						Gv4	0.66		
						Pgv4	0.9		
						Gv5	0.8		
						Pgv5	0.98		
						Gv6	1		
						Pgv6	1		

Inside the Soda exciter, and how to simulate its operation on a computer





Figure 7-1—Type ST1A—Potential-source, controlled-rectifier exciter

A Successful simulation of our simulated output interpreting the measured input to provide a similar output. Gray output is field data, and blue is simulated




Testing to prove models.

We use a number of field tests to verify our models:

1. Saturation test
2. Inertia test
3. Current interruption test
4. Steady state tests
5. 'Bump' tests

Saturation Test

Open Circuit Values




Calculated unsaturated field current @ 1 PU terminal volts	322 Amps
Measured saturated field amps @ 1 PU terminal volts	372 Amps
Calculated unsaturated field current @ 1.2 PU terminal volts	399 Amps
Calculated saturated field current @ 1.2 PU terminal volts	532 Amps
Saturation factor @ 1 PU terminal volts (SE1.0)	0.12
Saturation factor @ 1.2 PU terminal volts (SE1.2)	0.33
Resistance normalized to 75°C	0.16 Ω
Calculated Field Voltage corresponding to 1 PU unsaturated field current	53.3V

Inertia test

Load Rejection test


A load rejection by sudden removal of generator from the grid via generator breaker is performed to determine the machine's turbine-generator combined inertia of the unit. The machine was set to 15 MW, and at unity power factor. The generator breaker was opened and the unit was allowed to overspeed. The resulting trend shows the acceleration of the machine, which is used to calculate the inertia.

$$\text{Inertia PU} = \frac{\text{Initial MW} / \text{MVA base}}{2 * \left(\frac{\text{Hz PU}}{\text{seconds}} \right)}$$




Current Interruption

This waveform capture represents the positive half of peak-peak terminal voltage waveform during current interruption, which is used to determine the transient and synchronous parameters of the generator.




This waveform capture represents the peak to peak terminal voltage and current waveform when the breaker is initially opened, and is used to identify the subtransient reactance of the generator.



Vee Curves from Steady State

Vee-Curve analysis

Generator vee-curves were constructed using data collected at 5 different MW values. At each MW setting, the generator was first placed at the minimum allowable MVAR value, and values for MW, MVAR, Field amps and Terminal volts were recorded as the machine was adjusted up in increments of 3 MVAR to the maximum allowable MVAR value.








Fig. 5-55. Phasor diagram for salient-pole generator, neglecting r_a .

Bump Tests



Bump Tests

The following Caption shows response of OEL when a 10% step response was attempted.



Test Equipment

- Consider:
 - 1. resolution
 - 2. data storage and retrieval
 - 3. safety
 - 4. ease of operation